

**CEG-16
CUSTOMER SPECIFICATION**

II

TABLE OF CONTENTS

- 1. APPLICATION
- 2. MODEL NUMBER
 - 2.1 Customer
 - 2.2 Varex Imaging CEG-16
- 3.0 INSERT
 - 3.1 Physical
 - 3.2 Anode
 - 3.3 Electrical
 - 3.4 Filament (Cathode)
 - 3.5 Input Rates
 - 3.6 Vacuum Quality
- 4.0 HOUSING ASSEMBLY
 - 4.1 Physical
 - 4.2 Outline Drawing
 - 4.3 X-ray Beam
 - 4.4 Inherent Filtration
 - 4.5 Electrical
 - 4.6 Cooling
- 5.0 TESTING
 - 5.1 Final Acceptance Test
 - 5.2 Customer Acceptance Test

**CEG-16
CUSTOMER SPECIFICATION**

TABLE OF CONTENTS

6.0 SEASONING & DAILY WARM-UP

6.1 Seasoning Procedure

7.0 SYSTEM DATA

7.1 Thermal

7.2 Modifications

7.3 Regulatory

7.4 Label

7.5 Documents

8.0 RETURN PROCEDURE

8.1 Defective Units

9.0 REVISION

Addendum A

Addendum B

**CEG-16
CUSTOMER SPECIFICATION**

III

1.0 APPLICATION

1.1 The specification applies to the X-ray Tube Model CEG-16.

2.0 MODEL NUMBER

2.1 Customer CEG-16

2.2 Varex Imaging CEG-16

2.3 CEG-16 Assembly

2.3.1 Tube Unit 158002

3.0 INSERT

3.1 Physical

3.1.1 Cathode grounded, end window, Syltherm HF cooled irradiation X-ray tube.

3.2 Anode

3.2.1 The anode is Copper with the target material attached. The anode is cooled with Syltherm HF.

3.2.2 Target Material Tungsten

3.2.3 Target surface is parallel to the Beryllium window

3.3 Electrical

3.3.1 kVP Maximum Anode-to-ground 180 kVP

3.4 Filament (Cathode)

3.4.1 The filament is Tungsten and the leads are insulated from the grounded support and focusing structure, but must be maintained at ground potential.

3.4.2 Typical Operating Voltage Range 20-35 Volts DC

3.4.3 Typical Operating Current Range 7-10 Amperes

3.4.4 Maximum Filament Current 11.5 Amperes

**CEG-16
CUSTOMER SPECIFICATION**

(in-rush current limit required)

3.4.5	Insulation Resistance at 500 VDC	Filament to ground > 500 MΩ Target to ground > 500 MΩ Filament to target > 500 MΩ
3.4.6	Filament Characteristics	Refer to Figure 1
3.5	Input Rates	
3.5.1	Maximum Load	16,000 Watts
3.5.2	Operating kV Range (at 16kW max)	120 – 180 kV
3.5.3	Rating Charts	Refer to Figure 2
3.6	Vacuum Quality	
3.6.1	Maximum Pressure	1.0 x 10 ⁻⁴ Torr
3.6.2	Degradation Limit	
3.6.2.1	No more than one logarithmic scale in Torr	
4.0	HOUSING ASSEMBLY	
4.1	Physical	
4.1.1	Weight	122 lbs. (55 kg)
4.2	Outline Drawing	Refer to Figure 3
4.3	X-ray Beam	
4.3.1	Target to Window Distance	36 mm
4.3.2	Be Window Opening	146 mm
4.4	Inherent Filtration	4.32 mm Beryllium
4.5	Electrical	
4.5.1	Cable Receptacles	
4.5.1.1	Anode	R28

**CEG-16
CUSTOMER SPECIFICATION**

	4.5.1.2	Filament	62" No. 14 AWG
4.6		Cooling	
	4.6.1	Anode and Cathode Cooling Flow Minimum	19 L/min
	4.6.1.1	Fittings: PARKER Nipple - FF-502-10FO PARKER COUPLER - FF-501-10FO	
	4.6.2	Cooling Medium	Syltherm HF
	4.6.3	Cooling Temperature at Inlet (Max)	35°C
	4.6.4	Pressure at Inlet (Max)	6 Bar
5.0		TESTING	
	5.1	Final Acceptance Test	
	5.1.1	Stability	
	5.1.1.1	180kV, 89mA for 1 hour	0 Arcs Max
	5.2	Customer Acceptance Test	
	5.2.1	Stability 180kV, 89mA for 1 hour	0 Arcs Max
	5.2.2	Radiation Leakage Test	
	5.2.2.1	Customer is responsible for compliance with domestic and/or international cabinet X-ray regulations (responsibility of the customer) and shall be achieved at the system level.	
6.0		SEASONING & DAILY WARM-UP	
	6.1	Seasoning Procedure	Refer to Figure 4
7.0		SYSTEM DATA	
	7.1	Thermal	
	7.1.1	Maximum System Heat Generated	16,000 Watts
	7.2	Environmental Limits	

**CEG-16
CUSTOMER SPECIFICATION**

- 7.2.1 Operating Limits (must be non-condensing environment)
 - 7.2.1.1 Temperature 5°C to 40°C
 - 7.2.1.2 Humidity 30% to 90%
- 7.2.2 Shipping & Storage Limits (Be window Vacuum Cap is required)
 - 7.2.2.1 Temperature -10°C to +70°C
 - 7.2.2.2 Humidity 10% to 95%

7.3 Modifications

- 7.3.1 It is necessary to consult with Varex Imaging for any technical modifications to the tube.

7.4 Regulatory

- 7.4.1 RoHS and REACH

7.5 Label - Each unit will be labeled with the following:

- 7.5.1 Serial/Model Number Refer to Figure 5
- 7.5.2 Be Label Refer to Figure 5

7.6 Documents - Each unit will be shipped with the following documents:

- 7.6.1 Tube Service Report 133232
- 7.6.2 Customer Data Sheet Refer to Figure 6

8.0 RETURN PROCEDURE

8.1 Defective Units

- 8.1.1 If the unit fails to meet the requirements specified in Section 2.0 through 7.0. The unit will be returned to Varex Imaging with a completed X-ray Test Checklist.
- 8.1.2 Returned units shall be packed in original shipping cartons.

CEG-16
CUSTOMER SPECIFICATION

9.0 REVISION

A

1. Establish.

B

1. Update Be thickness.

CEG-16
CUSTOMER SPECIFICATION




Figure 1 Filament Characteristics

**CEG-16
CUSTOMER SPECIFICATION**




Figure 2 Rating Chart

CEG-16
CUSTOMER SPECIFICATION




Figure 3 Outline Drawing (10013029)

**CEG-16
CUSTOMER SPECIFICATION**

Schedule for Warm-up

Warm-up should be run after 24 hours of idle time.

kV	mA	Ramp (min)	Hold (min)
75	10	0.5	2
125	40	0.5	2
170	40	0.5	2
180	40	0.5	2


Figure 4 Schedule for Warm-Up

CEG-16
CUSTOMER SPECIFICATION

Test
Design

Test
Design

VAREX IMAGING	
TYPE	CEG-16
PART No	158002
MANUFACTURED	NOVEMBER 2024
NORM. VOLTAGE	180 kV
POWER	16 kW
INH. FILTRATION	2.54mm Be
FILAMENT A (V)	10A
FOCAL SPOT	80mmOD 36mmID
SERIAL No	00000-1P



4122 AG


130080 A

Design

Design

F/A Document No. 30016562
Revision AB
10016416-AA

Product: CEG-16
Tube Unit
Template: Tube_SLC_CMN_39



F/A No. 158002
Serial No. 00000-1P
Plant No. SLC TUBE

Figure 5 Labels

**CEG-16
CUSTOMER SPECIFICATION**

51915-987-AA
P/N 158002

Tube Certification
Report CEG-16

Tube Type : CEG-16
Serial Number _____

<u>Item</u>	<u>Standard</u>	<u>Results</u>
Full Power Test	180 kV, 89 mA 60 min, 0 kicks	_____

Do Not Print - Not Compliant

Sign: _____

Date _____

Verify

Figure 6 Customer Data Sheet